

Foundation wall Booklet

Contents:

8' - 0" six inch cavity on footing

8' - 4" six inch cavity on footing

9' - 4" six inch cavity on footing


8' - 0" eight inch cavity on footing

8' - 4" eight inch cavity on footing

9' - 4" eight inch cavity on footing

Note:

These documents should look good printing with normal settings. If not change to higher quality printer settings.





8'- 0" Foundation wall using 6" concrete core Fox Blocks

6 rows of 16" block

Fox Blocks recommendations:


- 1 Rebar size & spacing as per Building Code.
- 2 If wall design exceeds Building Code follow site engineering.
- **3 -** Use 1st & 3rd horizontal rebar holders to the tension side of the wall unless site engineering specifies otherwise.
- 4 Footing size and rebar requirements as per building code and/or engineering.
- 5 Footing dowels as per building code and/or engineering.
- 6 Sill plate attachment as per Building Code.
- 7 Concrete strength as per Building Code.
- 8 Recommended concrete slump 5" to 6" (125 to 150 mm)
- 9 Maximum concrete lift heights and pour rates as per ACI code.
- **10 -** Below grade waterproofing / damp proofing as per Building Code.
- **11 -** Backfill after floor diaphragm is in place and 7 days of concrete cure as per most Building Codes.
- 12 Drainage tile/stone systems as per Building Code.

Rebar placement:

Horizontal - rebar holders will accept rebar sizes from #4 (10M) to #6 (20M) single or double mat of rebar

Vertical - #4 (10M) to unlimited, single or double mat of rebar (allowing for proper concrete placement & coverage)

Fox Blocks typically sees a single mat of #4 (10M) rebar used in both horizontal & vertical placement @ 16"o/c on the tension side of wall, depending on wall length and backfill height in non seismic areas.





8'- 4" Foundation wall using 6" concrete core Fox Blocks 6 rows of 16" block + 1 row of 4" straight block (height) extender

Fox Blocks recommendations:


- 1 Rebar size & spacing as per Building Code.
- 2 If wall design exceeds Building Code follow site engineering.
- **3** Use 1st & 3rd horizontal rebar holders to the tension side of the wall unless site engineering specifies otherwise.
- 4 Footing size and rebar requirements as per building code and/or engineering
- 5 Footing dowels as per building code and/or engineering.
- 6 Sill plate attachment as per Building Code.
- 7 Concrete strength as per Building Code.
- 8 Recommended concrete slump 5" to 6" (125 to 150 mm)
- 9 Maximum concrete lift heights and pour rates as per ACI code.
- 10 Below grade waterproofing / damp proofing as per Building Code.
- 11 Backfill after floor diaphragm is in place and 7 days of concrete cure as per most Building Codes.
- 12 Drainage tile/stone systems as per Building Code.

Rebar placement:

Horizontal - rebar holders will accept rebar sizes from #4 (10M) to #6 (20M) single or double mat of rebar

Vertical - #4 (10M) to unlimited, single or double mat of rebar (allowing for proper concrete placement & coverage)

Fox Blocks typically sees a single mat of #4 (10M) rebar used in both horizontal & vertical placement @ 16"o/c on the tension side of wall, depending on wall length and backfill height in non seismic areas.





9'- 4" Foundation wall using 6" concrete core Fox Blocks 7 rows of 16" block

Fox Blocks recommendations:


- 1 Rebar size & spacing as per Building Code.
- 2 If wall design exceeds Building Code follow site engineering.
- **3** Use 1st & 3rd horizontal rebar holders to the tension side of the wall unless site engineering specifies otherwise.
- 4 Footing size and rebar requirements as per building code and/or engineering
- **5** Footing dowels as per building code and/or engineering.
- 6 Sill plate attachment as per Building Code.
- 7 Concrete strength as per Building Code.
- 8 Recommended concrete slump 5" to 6" (125 to 150 mm)
- **9 -** Maximum concrete lift heights and pour rates as per ACI code.
- **10 -** Below grade waterproofing / damp proofing as per Building Code.
- **11 -** Backfill after floor diaphragm is in place and 7 days of concrete cure as per most Building Codes.
- 12 Drainage tile/stone systems as per Building Code.

Rebar placement:

Horizontal - rebar holders will accept rebar sizes from #4 (10M) to #6 (20M) single or double mat of rebar

Vertical - #4 (10M) to unlimited, single or double mat of rebar (allowing for proper concrete placement & coverage)

Fox Blocks typically sees a single mat of #4 (10M) rebar used in both horizontal & vertical placement @ 16"o/c on the tension side of wall, depending on wall length and backfill height in non seismic areas.





8'- 0" Foundation wall using 8" concrete core Fox Blocks

6 rows of 16" block

Fox Blocks recommendations:


- 1 Rebar size & spacing as per Building Code.
- 2 If wall design exceeds Building Code follow site engineering.
- **3** Use 1st & 3rd horizontal rebar holders to the tension side of the wall unless site engineering specifies otherwise.
- 4 Footing size and rebar requirements as per building code and/or engineering.
- **5 -** Footing dowels as per building code and/or engineering.
- 6 Sill plate attachment as per Building Code.
- 7 Concrete strength as per Building Code.
- 8 Recommended concrete slump 5" to 6" (125 to 150 mm)
- 9 Maximum concrete lift heights and pour rates as per ACI code.
- **10 -** Below grade waterproofing / damp proofing as per Building Code.
- 11 Backfill after floor diaphragm is in place and 7 days of concrete cure as per most Building Codes.
- 12 Drainage tile/stone systems as per Building Code.

Rebar placement:

Horizontal - rebar holders will accept rebar sizes from #4 (10M) to #6 (20M) single or double mat of rebar

Vertical - #4 (10M) to unlimited, single or double mat of rebar (allowing for proper concrete placement & coverage)

Fox Blocks typically sees a single mat of #4 (10M) rebar used in both horizontal & vertical placement @ 16"o/c on the tension side of wall, depending on wall length and backfill height in non seismic areas.





8'- 4" Foundation wall using 8" concrete core Fox Blocks 6 rows of 16" block + 1 row of 4" straight block (height) extender

Fox Blocks recommendations:


- 1 Rebar size & spacing as per Building Code.
- 2 If wall design exceeds Building Code follow site engineering.
- **3** Use 1st & 3rd horizontal rebar holders to the tension side of the wall unless site engineering specifies otherwise.
- 4 Footing size and rebar requirements as per building code and/or engineering.
- 5 Footing dowels as per building code and/or engineering.
- 6 Sill plate attachment as per Building Code.
- 7 Concrete strength as per Building Code.
- 8 Recommended concrete slump 5" to 6" (125 to 150 mm)
- 9 Maximum concrete lift heights and pour rates as per ACI code.
- 10 Below grade waterproofing / damp proofing as per Building Code.
- 11 Backfill after floor diaphragm is in place and 7 days of concrete cure as per most Building Codes.
- 12 Drainage tile/stone systems as per Building Code.

Rebar placement:

Horizontal - rebar holders will accept rebar sizes from #4 (10M) to #6 (20M) single or double mat of rebar

Vertical - #4 (10M) to unlimited, single or double mat of rebar (allowing for proper concrete placement & coverage)

Fox Blocks typically sees a single mat of #4 (10M) rebar used in both horizontal & vertical placement @ 16"o/c on the tension side of wall, depending on wall length and backfill height in non seismic areas.





9'- 4" Foundation wall using 8" concrete core Fox Blocks 7 rows of 16" block

Fox Blocks recommendations:

- 1 Rebar size & spacing as per Building Code.
- 2 If wall design exceeds Building Code follow site engineering.
- **3** Use 1st & 3rd horizontal rebar holders to the tension side of the wall unless site engineering specifies otherwise.
- 4 Footing size and rebar requirements as per building code and/or engineering.
- 5 Footing dowels as per building code and/or engineering.
- 6 Sill plate attachment as per Building Code.
- 7 Concrete strength as per Building Code.
- 8 Recommended concrete slump 5" to 6" (125 to 150 mm)
- 9 Maximum concrete lift heights and pour rates as per ACI code.
- 10 Below grade waterproofing / damp proofing as per Building Code.
- 11 Backfill after floor diaphragm is in place and 7 days of concrete cure as per most Building Codes.
- 12 Drainage tile/stone systems as per Building Code.

Rebar placement:

Horizontal - rebar holders will accept rebar sizes from #4 (10M) to #6 (20M) single or double mat of rebar

Vertical - #4 (10M) to unlimited, single or double mat of rebar (allowing for proper concrete placement & coverage)

Fox Blocks typically sees a single mat of #4 (10M) rebar used in both horizontal & vertical placement @ 16"o/c on the tension side of wall, depending on wall length and backfill height in non seismic areas.